


## UNPACKING AND REMOVING THE UNIT FROM THE PALLET



Removable parts of packaging



**Perform this action safely with two people for larger types**

Remove the crate from the unit by taking of the following parts:

- wooden top plate and protection
- vertical beams and protection
- slide unit down from plank-bridge base construction

Follow the instructions as given.

After the unit is unpacked, you can apply the accessories as shown in the pictures on the separate instruction sheet.



### WARNING

Read the instructions before using the machine.

1



**Remove side beams 2x**

2



**Remove top plate**

3




**Remove protection top**

4




**Remove vertical beams and protection on front side**

5



**Remove vertical beams and protection on backside**

6



**Remove outer screw 4x2  
Leave middle screw in place**



**WARNING**

Prevent the unit from rolling away on the casters.



7




**Place vertical beam under cabinet  
On both sides**

10



**Tilt cabinet slightly  
Place under front wheels of cabinet**

8




**Front view  
1 beam left + 1 beam right**

11



**Carefully slide unit onto floor**

9



**Flatten 2 remaining beams**

12



**Remove remaining screws**

13



**Remove metal brackets 4x**

14



**Remove protection foil**

15



**Remove screws (3x)**

16



- a) Remove safety beam front and shelves
- b) Remove protection foil of the shelves